



## NE 119<sup>th</sup> Street CRP (50<sup>th</sup> Ave to 72<sup>nd</sup> Ave)

**Location:** Central

**Number:** 25-2015-0038

**GL Number:** 409-000-189-00-01-29

**Phase:** Construction

**Project Manager:** Vanessa Johnson

**County Project Manager:** Robin Washington

**GSP Basin:** Basins 8-Barberton, 28-St Johns,  
50-Curtin Creek W

**Capital Improvement Project**

General Facilities

District Installed Infrastructure

Septic Elimination Program

Developer Reimbursement Program

**Restoration & Replacement Project**

Restoration & Replacement - Gravity

Restoration & Replacement – PS & FM

Restoration & Replacement – Fleet & Facilities

### Project Definition:

Objective. Serve the NE 119<sup>th</sup> Street corridor in association with the NE 119<sup>th</sup> Street County Road Project (CRP).

Scope of Work. Extend force main, gravity trunk and gravity main in NE 119<sup>th</sup> Street from NE 50<sup>th</sup> Avenue to NE 72<sup>th</sup> Avenue.

Project Statistics. Gravity trunk – 800 feet of 10-inch gravity trunk. Gravity main – 1,350 feet of 8-inch gravity main, 500 feet of which is over existing deep sewer main (to provide local service). Force main – 1,900 feet of 8-inch force main. 7 – 8-inch stubs for future development and 29 - 4-inch laterals in NE 119<sup>th</sup> Street for local service.

**Photos: (Map of area on the reverse side)**

### Budget Information:

Project Cost Estimate:

Total Project Cost:	\$973,000
Construction Cost:	\$820,000
Basis of Estimate:	Bid
Date of Estimate:	Sept. 2017

### Schedule Information:

<u>Activity</u>	<u>Year</u>
Predesign	2015
Permitting	2016-2017
Real Property/ROW	2016-2017
Design	2016-2017
Bid	2017
Construction	2017-2018

