

# **Clark Regional Wastewater District**

Six-Year Capital Program
Capital Project Profile

## DCWTS Phase 2B (CIP 2-1603B)

Location: Central and Ridgefield	Capital Improvement Project ⊠
Number: <u>27-2021-0074</u>	General Facilities ⊠
<b>GL Number:</b> <u>409-000-189-00-01-54</u>	District Installed Infrastructure $\Box$
	Septic Elimination Program $\Box$
Phase: Predesign	Developer Reimbursement Program $\Box$
	Fleet & Facilities □
Project Manager: Dale Lough	Restoration & Replacement Project
	Restoration & Replacement - Gravity $\Box$
	Restoration & Replacement – PS & FM $\Box$
<b>GSP Basin:</b> <u>Legacy – 2-1603</u> ,	Restoration & Replacement – Fleet & Facilities □

### **Project Definition:**

<u>Background.</u> Components of the Discovery Corridor Wastewater Transmission System (DCWTS) constructed during the DCWTS Phase 1 project require capacity upgrades to accommodate growth in the service area and redirection of the Ridgefield Treatment Plant. This project addresses upgrades to the Legacy pump station and force main system to increase the firm capacity from 5.9 MGD to 8.2 MGD.

<u>Objective.</u> Upgrade the capacity of the Legacy pump station and force main system. Address current facility deficiencies and enhance monitoring of the facility.

<u>Scope of Work.</u> Install a 20-inch force main, pigging and flow meter vault, motorized valves; replace existing slide gate.

Project Statistics. 3,650 feet of 20-inch force main assumed, pigging and flow meter vaults.

#### **Photos:** (on the reverse side)

#### **Budget Information:**

#### Project Cost Estimate:

Total Project Cost: \$6,375,000
Construction Cost: \$4,900,000
Basis of Estimate: Predesign
Date of Estimate: Mar. 2023

## **Schedule Information:**

<u>Activity</u>	<u>Year</u>
Predesign	2021-2022
Permitting	2022-2026
Real Property/ROW	2022-2026
Design	2022-2026
Bid	2027
Construction	2027


**NOTE: NEED TO UPDATE FIGURE** 

Updated: Sept 2023



# **Clark Regional Wastewater District**

Six-Year Capital Program Capital Project Profile



Updated: Sept 2023