



### NE 179<sup>th</sup> Street Trunk

**Location:** Central

**Number:** TBD

**GL Number:** TBD

**Phase:** Planning

**Project Manager:** Les MacDonald

**GSP Basin:** Whipple Creek East - 2-1605

**Capital Improvement Project**

General Facilities

District Installed Infrastructure

Septic Elimination Program

Developer Reimbursement Program

Fleet & Facilities

**Restoration & Replacement Project**

Restoration & Replacement - Gravity

Restoration & Replacement – PS & FM

Restoration & Replacement – Fleet & Facilities

#### Project Definition:

Background. The District’s 2017 General Sewer Plan identifies a gravity sewer and pressure sewer to be installed in NE 179<sup>th</sup> Street. The District is completing a developer installation of the trunk line east of the NE 29<sup>th</sup> Avenue intersection in conjunction with Clark County’s NE 179<sup>th</sup> Street and NE 29<sup>th</sup> Avenue Intersection Improvement Project.

Objective. Extend sewer service in support of development along the NE 179<sup>th</sup> Street corridor.

Scope of Work. Install 770 feet of 10-inch gravity sewer, 650 feet of 8-inch gravity sewer, and 690 feet of 6-inch force main to accommodate development along the NE 179<sup>th</sup> Street corridor.

Project Statistics. Gravity Sewer – 1,300 feet of 12-inch and 750 feet of 15-inch gravity sewer.

#### Photos: (on the reverse side)

#### Budget Information:

Project Cost Estimate:

Total Project Cost:	\$850,000
Construction Cost:	\$850,000
Basis of Estimate:	
Date of Estimate:	Sept. 2023

#### Schedule Information:

Activity

Year

Predesign	By Others
Permitting	By Others
Real Property/ROW	By Others
Design	2023-2024
Bid	By Others
Construction	2024

