



McCormick Creek Pump Station (CIP 3-612A)

Location: Ridgefield

Number: TBD

GL Number: TBD

Phase: Planning

Project Manager: Les MacDonald

GSP Basin: Boschma – 3-610
McCormick Creek – 3-612

Capital Improvement Project

General Facilities

District Installed Infrastructure

Septic Elimination Program

Developer Reimbursement Program

Fleet & Facilities

Restoration & Replacement Project

Restoration & Replacement – Gravity

Restoration & Replacement – PS & FM

Restoration & Replacement – Fleet & Facilities

Project Definition:

Background. Identified in 2017 General Sewer Plan to provide service to a larger basin that is currently served by an interim pump station.

Objective. Extend service to the eastern portion of the City of Ridgefield.

Scope of Work. This project includes developer reimbursement for a pump station and force main along N 10th Street in association with the proposed Greely Farms residential subdivision. The project scope includes decommissioning of the Greely Acres Interim Pump Station.

Project Statistics.

Force main: 3,500 feet of 6-inch force main.

Pump Station: Decommissioning of the Greely Acres Interim Pump Station.

12 hp duplex submersible pumps for 260 gpm at startup and 370 gpm at buildout; 8-foot wet well; three phase electrical service; diesel generator; control kiosk; odor control chemical tank.

Photos: (Map of area on the reverse side)

Budget Information:

Project Cost Estimate:

Total Project Cost:	\$1,700,000
Construction Cost:	\$1,700,000
Basis of Estimate:	Planning
Date of Estimate:	Sept. 2023

Schedule Information:

Activity

Year

Pre-design	By Others
Permitting	By Others
Real Property/ROW	By Others
Design	2023-2024
Bid	By Others
Construction	2024

